



# ANCHORAGE PORT MODERNIZATION PROJECT

NORTH EXTENSION STABILIZATION STEP 1  
PROGRESSIVE DESIGN BUILD INDUSTRY OUTREACH

**AUGUST 4, 2016**





# AGENDA

1. Introduction of Project Team
2. Purpose of Meeting
3. APMP Phasing
4. APMP Phase 1 Funding & Permitting
5. NES Step 1 Project Description
6. NES Step 1 Status to Date
  - Engineering & Surveying
  - Environmental
  - Geotechnical
7. Progressive Design Build (PD/B) Procurement for the NES Step 1
  - Why PD/B for NES Step 1?
  - Overview of PD/B
  - Procurement Step 1
  - Procurement Step 2
  - Procurement Schedule
  - Pre-RFP Site Visit
8. Questions



Anchorage Port Modernization Project

## **PURPOSE OF MEETING**



# PURPOSE OF MEETING

- Advance notice of upcoming procurement to facilitate fast track schedule
- Provide overview of the APMP and the NES Step 1
- Describe planned delivery method for NES Step 1
- Seek Industry Feedback




Anchorage Port Modernization Project

## **APMP OVERVIEW**

# APMP PHASE 1: NORTH EXTENSION STABILIZATION STEP 1 + PETROLEUM/CEMENT TERMINAL


2017-2018 CONSTRUCTION





# APMP PHASE 2: TERMINAL 1 + TERMINAL 2

2018-2022 CONSTRUCTION



# APMP PHASE 3: PETROLEUM TERMINAL

2019 OR LATER CONSTRUCTION

NORTH EXTENSION

TERMINAL 2  
TOTE BERTH

TERMINAL 1  
MATSON BERTH


REPLACEMENT  
POL 2

POL 1 &  
CEMENT BERTH



# APMP PHASE 4 + 5: NORTH EXTENSION STABILIZATION STEP 2 & T3 DEMO

2020 OR LATER CONSTRUCTION





# APMP PHASE 1 FUNDING AND PERMITTING


- Full funding is available for Phase 1
- Permitting
  - 2017 Landside Construction
    - Section 408 Permit Application has been submitted
  - 2018 Waterside Construction
    - Section 10/404 Permit Application to be submitted in Spring 2017
    - Incidental Harassment Authorization Permit Application to be submitted Spring 2017
  - PD/B Team integration with permitting anticipated
  - Potential need to modify permit applications as design develops



Anchorage Port Modernization Project


## **APMP PHASE 1 NES PROJECT DESCRIPTION**

## PROJECT LOCATION & STAGING AREA





# APMP PHASE 1 - NES CONSTRUCTION





# CONCEPT PLAN CONSTRUCTION

Assumed first year of construction:

- Install 1150 LF of new Cellular Sheet Pile Bulkhead
  - Length of sheets for new bulkhead is approx. 60'
  - Height of exposed face is approx. 30'
- Diameter of new Cellular Sheet Pile Bulkhead ~ 80'
  - Number of Cellular Sheet Pile Cells = 12
- Stockpiled excess sheetpile from PIEP available for use by PD/B Team
- Install up to 500 LF of new cut-off Z-Pile Wall (or rock revetment)
- Grade Existing Uplands for positive drainage



# CONCEPT PLAN DEMOLITION

Assumed second year of construction:

- Excavation ~ 700,000 CY
- Dredging ~ 600,000 CY
- Maintain existing Bathymetry outside of Project Limits
- Material Disposal Options
- Salvage Armor Rock (for reuse as slope protection) = 1,500 CY
  - Salvage Riprap = 9,100 CY
  - Salvage and Stockpile Excavated Material (for Upland Expansions) = 35,000 CY
- Remove Open Cell Sheet Pile Wall (face length) = 800 LF
  - Remove Z-Pile Wall Structures = 250 LF
  - Number of Open Cells Removed = ~ 30



Anchorage Port Modernization Project

## **APMP PHASE 1 NES STATUS TO DATE**



# PROJECT STATUS TO DATE

## Engineering & Surveying

- Topographic and Control Survey available

- 15-percent Concept Plans available

## Environmental

- Limited information – expect PD/B Team action

- Permit applications under initial development – expect PD/B Team integration

## Geotechnical

- Large inventory of legacy data

- Limited information along bulkhead concept alignment – expect PD/B Team action



Anchorage Port Modernization Project

# **PROGRESSIVE DESIGN BUILD (PD/B) PROCUREMENT FOR THE APMP PHASE 1 NES CONSTRUCTION**







# WHY PROGRESSIVE DESIGN BUILD?

- Allocate the risk to the parties most capable of managing the risk
- Risk Management Process through advancement of design
- Allows selection of fully qualified teams
- Fully integrated team between Designer and Constructor
- Forms a positive collaborative team with the Owner, Designer and Constructor
- Ability to arrive at Guaranteed Maximum Price (GMP)


# CM/CG



# PROGRESSIVE DESIGN-BUILD



# PROGRESSIVE DESIGN-BUILD APPROACH





# PROCUREMENT STEP 1

- Request for Proposals & Short Listing
  - Selection based upon qualifications, experience, methodology and approach
    - Qualifications of the firm and key personnel
  - Short listing similar to a professional services selection
  - Short listed proposers will be notified and will advance to Step 2



# PROCUREMENT STEP 2

## Best Value Evaluation

- Second Proposal developed for detailed description of project approach with respect to addressing risks and technical challenges
- Possible interview for Short Listed Progressive Design Build Teams
- Cost Component for Best Value Selection
  - Based upon Overhead Rates and Fee
- Scoring anticipated to be approximately:
  - 20% to 30% Costs
  - 70% to 80% Technical



# PROCUREMENT SCHEDULE

- RFP Release – October 2016
- Step 1 Proposal Due – November 2016 (30-days following RFP Release)
  - Qualifications
  - Experience
  - Methodology & Approach
- Short List Notification – Mid December 2016
- Step 2 Proposal Due – January 2017
  - Execution Strategy
  - Cost Component (Fee & Overhead)
- Project Interviews (Optional) - January 2017
- Award – February 2017



# PRE-RFP SITE VISIT

- Week of September 19th
- Optional but encouraged
- Site familiarization prior to snow fall
- More information to be made available on the MOA Purchasing and Port websites

# QUESTIONS?



Thank You!

Todd Cowles, P.E.  
[cowlestc@muni.org](mailto:cowlestc@muni.org)